Bill of Quantity
Japan Pavilion / SFFF2014
Material list / Use specified materials (or equivalent) listed below
Date:

Example

Item	Item	Description	Qty	Unit	Unit Cost	Amount
1	**System Construction**					
a	System Wall(Include door and luck)	H2500	62	mR		
b	Sign Stand	H2500(Lightbox Sign Tower)	10	nos		
c	Ceiling beam with infill plywood(green)	D700	37.5	mR		
d	System info countor with lock	W1000xD500XH1000	14	nos		
2	**Flooring**					
a	Carpet	Standardcarpet Ral-Farden（or Equiv）	102	sqm		
3	**Wooden Fabrication**					
a	Information Wall	Wall (W1134+W1161+W1801)xH2500/Painted	1	nos		
b	Curved Tower	Sign Tower(R3050D800xH2500)/Painted	1	nos		
c	Information Counter	(W2525D1000H1000)/Painted+Cutting Sheet	1	nos		
d	DisplayBox（Inside Showcase）	(W1980D230H250)/Painted White	1	nos		
4	**Graphic**					
a	Main Sign(Large)	3300 (W) x 700 (Ht)	1	nos		
b	Main Sign(Small)	900 (W) x 80 (Ht)	1	nos		
c	Graphic for 1-b	W700xH2500	17	nos		
d	Corner Sign	W1500H450	14	nos		
e	Information Graphic Panel	W1980H950	1	nos		
f	Corner Sign for Acrylic plate	ϕ450	33	nos		
g	Name plate	Forex Panel w250h40 with Graphic Sheet	14	nos		
5	**Acrylic Plate**					
a	SignTower Acrylic Plate with Graphic	W700xH2500x19(transparenat-	36	nos		
b	BoothSign Acrylic Plate with Graphic	W1500xH495	14	nos		
c	Display Sign Acrylic Plate with Graphic	W1980xH950	1	nos		
d	Clear Acrylic plate for Display Corner	W1050xH700	2	nos		
6	**Lighting**					
a	Halogen Downlight DW70w		12	nos		
b	FL30w		102	nos		
c	50w -Halogen Arm Spotlight		42	nos		
d	Local Socket-A		21	nos		
e	D/B bix 15kva	32amp 220v/400vTPN 50hz Main Supply Inc,	1	nos		
7	**Furniture(rental)**					
	Table					
a	Round table	ϕ700mmH600mm	14	nos		
b	Square table	□700mm H700mm	1	nos		
	Chairs					
c	Folding Chair	Storage and Exhibit area	45	nos		
d	High stool	W450D450H700	2	nos		
	Others					
a	Water Sink	（include of Water supply fee）	1	nos		
b	Refrigerator		1	nos		
c	MicroWaveOven		1	nos		
d	Pegboad	boad	1	nos		
e	Catalogue stands		1	nos		
f	Rubbish bins		15	nos		
g	Big rubbish bins		1	nos		
h	Bin liners	1linerx30sheet	10	set		
i	Water Server	cold&Hot	1	set		
j	water bottle	water bottle	4	nos		
k	cup	x10	1	set		

8	**AV Equipment**					
a		50" Plasma TV with DVD Player	1	nos		
9	**Micellaneous**					
a	Installation&Dismantling labor	It is included stand by staff for the duration of	1	nos		
b	Material Transportation		1	nos		
c	White cloth	for each display table and counter	30	pcs		
10	**Water Supply**					
a	Water & Waste	0.5"Water&1.5"Waste to Clients own Single	1	nos		
b		Hire of Single Sink	1	nos		
11	**Telecommunications**					
a	Internet LAN	2M bps	1	nos		
12	Insurance for Exhibitor		1	no		
	TOTAL MAIN COST		l	A	SubTotal	
				B	VAT@20%	
				A+B	**Total**	